HaanJi: a voice receptionist for Indian small businesses that hears the business's own words, answers before the caller finishes, and can prove what was agreed

Aritra Hazra · Prabhav Upadhayay · Anuj Uniyal
B.Tech Information Technology (Artificial Intelligence), Medi-Caps University
Evaluation report, version 1.0 · 15 October 2026 · code and data: github.com/aritra-25hazra/haanji

Abstract

Small clinics, salons, laboratories and coaching institutes in India lose bookings because nobody answers the phone, and the callers who do get through speak Hinglish or Benglish and name services, doctors and neighbourhoods that no general-purpose speech recogniser has heard of. HaanJi is an open-source voice-agent engine built around three contributions that address the three reasons such an agent fails in practice. **Bhasha Bridge** builds a per-tenant phonetic index from the catalogue a business supplies at onboarding and uses it both to bias the recogniser and to repair its output, replacing a token only when the recogniser was unsure *and* the token's Indic-aware sound key matches a known form exactly. **Speculative Turn Execution** applies the idea of branch prediction to dialogue: read-only tools are predicted from partial transcripts and run while the caller is still speaking, and a speculative result is claimed only when the real turn requests byte-identical arguments. The **Pramaan Ledger** seals every write into an Ed25519-signed, hash-chained receipt that binds the action to the exact words with which the caller confirmed it, refuses writes that carry no such proof, and can be verified by anyone holding the public key. The contributions are evaluated with an ablation harness over 24 authored call scenarios in six vertical packs and three languages, repeated under 5 independent random seeds, and with a transcript-level experiment over 2,430 independently corrupted sentences per noise level. Against Soundex, Metaphone, Double Metaphone, NYSIIS and the edit-distance bound alone, with everything but the key held fixed, the Indic-aware key is the best on synthetic noise (every pairwise McNemar $p < 0.001$) and within a point of the classics on real recogniser output, where the safety rule matters more than the key. At 30% synthetic recognition noise Bhasha Bridge reduces the catalogue entity error rate from 32.6% to 0.82% (97.5% relative) with 99.1% correction precision and no harmful correction in any run, and raises end-to-end task success from 76.4% to 90.8%. Speculation lowers the median engine-side latency of read-only turns from 246 ms to 142 ms (42.3%) at a 41.9% hit rate without changing any transcript. The ledger detects 80 of 80 single-field tampering attempts, a deletion and a re-hashed forgery, and accepts zero unconfirmed writes. We also report the design and offline validation of a hosted-model dialogue adapter that preserves the ledger's guarantee by construction, A pilot of the real-recogniser pipeline (synthetic Indian-English speech through Whisper) found the bridge's confidence gate open and the layer making harmful corrections; three stated guards remove them, and on that data the bridge is safe and reduces entity errors by about an eighth. Handing the pack vocabulary to the recogniser as its prompt halves entity error before any repair, which makes biasing the lever and the bridge the safety net behind it; calibrating the bridge's confidence gate per recogniser does not help, and a sweep shows why: on Whisper's probabilities the gate contributes nothing to safety, the stated guards do. Under noise learned from real recognisers — including rural Hindi telephone speech from the public Gram Vaani corpus, which Whisper transcribes at about 80% word error with a quarter of the words dropped — the bridge removes 28–33% of the remaining entity errors at over 95% precision, against 97% under the authors' own corruption model; the report quotes both. We state plainly what the evaluation does not yet cover: real callers, real users, and vendor round-trip time.

1. Introduction

1.1 The problem

A typical Indian neighbourhood clinic receives tens of calls a day and answers a fraction of them. The receptionist is with a patient, it is lunch time, it is Sunday. The caller does not leave a voicemail; they call the next clinic. An automated receptionist that could answer in the caller's own mix of Hindi and English, find a slot, and book it would recover that revenue directly, and the economics are not subtle: at the call volumes of a small business the engine's own cost model puts an AI-answered call at roughly a third of the cost of a human-answered one.

Building such an agent from a speech recogniser, a language model and a speech synthesiser is now routine. Making it *trustworthy enough to take a booking* is not, and the reasons are specific to this setting:

1. **The vocabulary that matters is the vocabulary the recogniser has never seen.** The words on which a booking turns, the service ("root canal", "keratin treatment", "lipid profile"), the doctor ("Dr Sheikh"), the locality ("Bhawarkuan"), are exactly the words a general recogniser mangles, and it mangles them in systematic, Indian-English-specific ways: v/w, s/sh, aspirates, long vowels, a dropped initial /h/. Text-level word error rate understates the damage, because an agent can tolerate a hundred wrong function words and not one wrong service name.
2. **Latency is felt at the turn, not on average.** A caller who asks "kal subah ka time milega?" and waits a second and a half in silence hangs up or talks over the agent. Most of that time is spent in tools (availability lookups, catalogue queries) that could have started before the caller finished the sentence.
3. **"The AI booked it" is not an answer.** When a customer disputes an appointment, a log line is worth nothing; the business needs evidence of what was asked and what was agreed, and the customer needs to be unable to be booked for something they never confirmed, even if the dialogue logic has a bug.

1.2 Contributions

HaanJi is a complete, deployed system (a Python engine, a Java core API, a React owner console and a set of YAML vertical packs), but this report is about the three mechanisms in the engine that are, to our knowledge, not found together in any existing product, and about the evidence for them:

- **Bhasha Bridge** (§4), a per-tenant phonetic index with an Indic-aware key and a two-condition correction rule designed so that the layer can never damage a transcript the recogniser got right.
- **Speculative Turn Execution** (§5), prediction and early execution of read-only tools from partial transcripts, with four enforced properties (purity, argument identity, freshness, invalidation) that make it a pure latency optimisation.
- **Pramaan Ledger** (§6), signed, hash-chained receipts that bind every write to the caller's recorded confirmation, with a refusal path for unconfirmed writes and an independent verifier.

A fourth, smaller contribution is methodological: the engine ships with a benchmark harness (§3.4) that produces every number in this report from a clean checkout with no network and no API key, and a corruption model written independently of the correction layer so that the harness can catch the layer doing harm.

1.3 What this report is and is not

This is a report on an engineering artefact and its measured behaviour. Every number comes from `research/harness/report_data.py`, which runs the harness under 5 seeds and reports means with 95% confidence intervals; the single-seed figures quoted in the project README come from `python -m haanji.bench` and agree with them. The recognition noise is synthetic, the callers are scripted, and the latencies are engine-side. §8 says what follows from that, and §9 describes the two studies (real recordings, real users) that are planned to close the gap.

2. Background and related work

Contextual biasing in speech recognition. End-to-end recognisers can be steered towards a list of phrases supplied at request time, either inside the model (contextual listen-attend-spell, Pundak et al. 2018) or by shallow fusion with a phrase-level language model at decode time (Zhao et al. 2019). Commercial speech APIs expose this as "phrase hints". Biasing improves recall of in-list phrases but does nothing after the fact, and it is only as good as the recogniser's willingness to honour the list. Bhasha Bridge sends the same lexicon as hints *and* keeps a post-correction pass, because in our setting the recogniser is a vendor black box that may ignore the hints, may not offer them at all (browser Web Speech API), and in any case reports a confidence we can use.

Phonetic matching. Soundex (Russell 1918) and its descendants Metaphone and Double Metaphone (Philips 1990, 2000) map spellings to sound keys so that variant spellings collide. They encode English phonology. Hinglish spoken by Indian callers and transcribed by Indian-English recognisers merges distinctions English keeps (v/w, s/sh, dental/retroflex) and keeps some English merges apart; standard Soundex therefore both over- and under-merges. The key in §4.1 is a small explicit rule set for this

phonology, placed in source so that each rule is a stated, testable claim. Edit distance (Levenshtein 1966) is used as the second, surface-level condition.

Code-mixed and Indian-accented speech. Hindi-English code-mixing is the ordinary register of Indian urban speech (Bali et al. 2014). Recent datasets, IndicVoices (Javed et al. 2024) and the Svarah benchmark of Indian-accented English (Javed et al. 2023), document how far general recognisers, including Whisper (Radford et al. 2023), fall short on this speech, and particularly on named entities. These datasets are the natural next material for the correction layer (§9).


Speculative execution. Speculating on the likely branch and discarding the work if the guess is wrong is the oldest latency trick in computer architecture (Hennessy and Patterson 2017). It has recently been applied inside language-model inference as speculative decoding (Leviathan et al. 2023; Chen et al. 2023), where a cheap draft model proposes tokens that the large model verifies. Speculative Turn Execution applies the same shape one level up, at the dialogue turn: a cheap predictor proposes a tool call from a partial transcript, the tool runs early, and the real turn "verifies" by asking for identical arguments. The correctness argument is the same as in hardware: speculation must be side-effect-free and its results must be discarded unless the architectural path asks for exactly them.

Tamper-evident logs. Linking records by hash so that any alteration breaks the chain dates to Haber and Stornetta (1991); Merkle trees (Merkle 1987) make a set of records verifiable from one root; Certificate Transparency (Laurie, Langley and Kasper 2013) is the best-known deployment of a publicly verifiable append-only log. Ed25519 (Bernstein et al. 2012) provides small, fast signatures. The Pramaan Ledger is a conventional composition of these: per-tenant Ed25519 keys, a SHA-256 chain over canonical JSON (RFC 8785, Rundgren et al. 2020), and daily signed Merkle roots. What is new is not the cryptography but *what is sealed*: the receipt carries the agent's confirmation question and the caller's answer with timing and recognition confidence, and the ledger refuses to seal a write that carries no such confirmation.

Confirmation in spoken dialogue. Explicit confirmation before a consequential action, and the design of recovery from non-understanding, are long-standing concerns in spoken dialogue systems (Bohus and Rudnicky 2005; Skantze 2005). Task-oriented dialogue research measures success on benchmarks such as MultiWOZ (Budzianowski et al. 2018). HaanJi's dialogue policy is deliberately a deterministic state machine, with a hosted model as an optional, bounded replacement (§7); the confirmation step is never delegated to the model.

3. System overview

3.1 Architecture



One pass through `CallSession.handle_utterance` is the whole hot path. The engine is 5,775 lines of Python 3.11 with no vendor SDK outside its adapters; speech and language providers sit behind three protocols and are mocked by default, which is what makes the evaluation reproducible offline. A Java core API (2,772 lines) ports the ledger and exposes the owner-facing REST surface; a React console (1,324 lines of TypeScript) reads the engine directly. The whole system is deployed (engine on Render, console on Vercel) and has run live calls through a browser and through a WhatsApp webhook.

3.2 Vertical packs

A pack is one YAML file describing a kind of business: catalogue with durations and prices, staff, hours, persona, refusals and escalations, seed vocabulary (places, brands, phrases), a small knowledge base, and the scenarios the pack must pass before it ships. Five packs are included:

pack	language	services	staff	scenarios
dental_clinic	Hinglish	6	3	8
salon_spa	Hinglish	6	4	4
diagnostic_lab	Hinglish	6	3	3
coaching_institute	Hinglish	4	3	3
clinic_kolkata	Benglish	4	2	3
clinic_pune	Marathinglish	4	2	3

The Kolkata and Pune packs are the test of the claim that the engine knows nothing about any particular language: supporting Benglish, and then Marathinglish, took a phrase-table row and one YAML file each, with no engine code forked. (The Pune pack was added after the evaluation runs below, which cover the first five packs and 21 scenarios; the selftest covers all 24.)

3.3 The dialogue policy and guardrails

The default dialogue policy is a deterministic state machine over the conversation context (service, date, time, staff, name, phone, pending confirmation). It is deterministic for three reasons that matter for a system that takes bookings: every decision is reproducible, so a regression is a bug and not a sampling accident; it is the thing the ledger audits; and it runs in microseconds, leaving the latency budget for the parts that need it. Guardrails run on the corrected transcript *before* the policy: each rule pairs a subject pattern with a qualifier so that "report kab milegi" (scheduling) is allowed while "report mein sugar zyada hai, khatra hai kya" (diagnosis) is refused and handed off.

3.4 The evaluation harness

`haanji.bench` runs the same calls through four configurations, switching one contribution off at a time (`full`, `no_speculation`, `no_bhasha`, `baseline`), and measures:

- **Entity error rate (EER).** The fraction of catalogue entities (services, staff, places) in what the caller actually said that the transcript gets wrong, counting both misses and spurious entities. Word error rate is the wrong instrument: the agent has to get the *entities* right, not the function words.
- **Task success.** Whether the call reaches the outcome its scenario expects (BOOKED, FAQ_ANSWERED, LEAD_CAPTURED, HANDED_OFF).
- **Turn latency.** From the end of the caller's speech to the agent's reply, in *nominal* milliseconds: simulated audio runs at a time scale (90× here) and is converted back, so a 1-minute call takes under a second to benchmark without changing the arithmetic.
- **Correction quality.** Every correction the bridge makes is classified as beneficial (produced a gold entity), neutral, or **harmful** (overwrote a span the recogniser had heard correctly). The harmful count is the number the design is judged by.
- **Speculation hit rate, wasted speculations, saved time**, and **unconfirmed writes**: bookings that reached the business without a sealed receipt, which the harness actively tries to produce.

Two sources of recognition error are used. The *authored* scenarios carry corruptions written by hand (the right material for a demo, a weak basis for a claim, since the author of the corruption is also the author of the repair). The *corruption model* (`haanji/corrupt.py`) generates errors independently from a list of substitutions that are properties of the language, not of this system: v/w, s/sh, aspirate loss, long-vowel shortening, c/k, ai/e, initial-h deletion. It corrupts content words indiscriminately, including words in no lexicon, and never touches the grammar words that carry the dialogue. The transcript-level experiment applies it to a corpus built from every service, staff member and place in every pack in eight sentence frames, so the measurement is not dominated by whichever phrases a scenario author wrote.

Everything below was produced by `research/harness/report_data.py` with 5 independent seeds and 3 repetitions per seed, on one laptop, with no network and no API key. Values are mean ± 95% confidence interval (t-distribution over seeds). The data file is `research/report_data.json`; the figures are plain SVG written by the same script.

4. Bhasha Bridge

4.1 Method

The index. At onboarding the pack's services (with aliases), staff, places, brands and phrases are turned into a `TenantLexicon`: each surface form is stored with a type prior and a phonetic key. The key (`phonetics.py`) applies an ordered list of normalisation rules before encoding: long vowels shorten (`aa`→`a`, `ee`→`i`, `oo`→`u`); `ph`→`f`; v and w merge; s, sh and z merge; ch/chh merge; dental and retroflex t/d/th/dh collapse; k/kh/q/c-before-back-vowel merge; g/gh merge; b/bh/p merge; n/m merge; l/r merge; h and y are dropped; a word-initial vowel is bucketed as `A` because a weak initial /h/ is dropped by speakers and recognisers alike (*haircut* / *ercut*). Vowels after the first position are then removed and runs collapsed, Soundex-style. Multi-word entities get a concatenated phrase key. Every rule is a stated claim about Indian pronunciation and lives in source so it can be argued with.

Biasing. The lexicon's surface forms are handed to the recogniser as hints (capped at 60). The mock recogniser honours them by raising confidence on in-lexicon words, which is what a real biased decoder does; the browser recogniser used by the live demo cannot take hints at all, which is the case the post-correction pass exists for.

Correction. The bridge scans the final transcript for n-grams (n ≤ 3, longest first) and replaces a span only when **both** of two independent conditions hold:

1. the recogniser's confidence in the span is below 0.85, and
2. the span's phonetic key equals a lexicon key exactly, and the surface edit distance to that lexicon form is at most 2 (3 for multi-word spans).

Grammar words are never touched, and neither is anything that follows a name introduction ("mera naam …"), so a caller called Wijay is not corrected to the locality Vijay Nagar. Either condition alone produces false corrections; the harness is built to count them.

4.2 Results: transcript level

Table 1 — Transcript-level correction (Bhasha Bridge alone)

noise rate	sentences	entities	EER off (%)	EER on (%)	reduction (%)	precision (%)	harmful
15%	2430	3303	16.8 ± 1.7	0.37 ± 0.14	97.8 ± 0.9	99.2 ± 0.6	0.0
30%	2430	3303	32.6 ± 0.7	0.82 ± 0.13	97.5 ± 0.4	99.1 ± 0.3	0.0
45%	2430	3303	48.7 ± 2.9	1.93 ± 0.17	96.0 ± 0.4	99.1 ± 0.1	0.0




Figure 1. Entity error rate on independently corrupted sentences, Bhasha Bridge off and on. Whiskers are 95% CIs over seeds.

At 30% noise, 2,430 sentences carrying 3,303 catalogue entities go from 32.6% entity error to 0.82%, a 97.5% relative reduction, at 99.1% precision (the fraction of corrections that produced a gold entity). The improvement is not noise: on the paired per-sentence outcomes at 30% noise, 936 sentences go

from wrong to right and 0 from right to wrong (McNemar p < 0.001; `research/harness/stats.py`). The harmful count, the number of times the layer overwrote a span the recogniser had right, is zero in every seed at every noise level; the confidence intervals on it are zero because the value never moved. The median cost of the pass is 0.07 ms per utterance. The residual error is almost entirely entities the corruption model damaged beyond edit distance 2, or whose corrupted form collided with no lexicon key, which the second condition correctly refuses to touch.

4.3 Results: end to end

Table 2 — End-to-end calls under the same noise (Bhasha on vs off)

noise rate	calls	EER off (%)	EER on (%)	task success off (%)	task success on (%)	beneficial	neutral	harmful
15%	72	16.9 ± 6.6	0.0 ± 0.0	87.5 ± 4.4	95.8 ± 1.7	9.2	0.8	0.0
30%	72	33.8 ± 9.2	0.0 ± 0.0	76.4 ± 9.4	90.8 ± 7.1	18.2	2.8	0.0
45%	72	50.2 ± 3.7	0.0 ± 0.0	59.7 ± 5.2	81.1 ± 3.4	25.4	3.4	0.0




Figure 2. Calls reaching their expected outcome under the same noise, Bhasha Bridge off and on.

In full calls the same noise is applied to every caller turn and the dialogue has to survive it. Without the bridge, task success falls with noise, from 87.5% at 15% to 59.7% at 45%, because a mangled service name sends the policy down the wrong path or into a clarification the scripted caller does not answer. With it, success stays at 90.8% at 30% noise and 81.1% at 45%. The calls that still fail with the bridge on are ones where the corruption hit a word outside the lexicon that the policy nonetheless needed (a date word, a number), which the bridge rightly leaves alone; §9 discusses this.

Table 3 — Per pack at 30% noise

pack	language	calls	task success off (%)	task success on (%)	EER off (%)	EER on (%)
clinic_kolkata	benglish	9	75.6 ± 15.1	88.9 ± 16.9	36.7 ± 9.3	0.0 ± 0.0
clinic_pune	marathinglish	9	62.2 ± 15.8	77.8 ± 13.8	43.3 ± 23.6	0.0 ± 0.0
coaching_institute	hinglish	9	82.2 ± 15.7	91.1 ± 15.1	26.7 ± 34.6	0.0 ± 0.0
dental_clinic	hinglish	24	70.0 ± 17.3	90.0 ± 8.6	34.4 ± 17.8	0.0 ± 0.0
diagnostic_lab	hinglish	9	91.1 ± 6.2	97.8 ± 6.2	20.0 ± 22.7	0.0 ± 0.0
salon_spa	hinglish	12	85.0 ± 8.7	98.3 ± 4.6	31.1 ± 15.1	0.0 ± 0.0

The per-pack view at 30% noise shows the mechanism is not tuned to the dental pack the demo uses: the Benglish pack gains as much as the Hinglish ones, from a lexicon that contains Bengali-English surface forms and the same key rules, and the Marathinglish pack, the hardest row because its scenarios carry the most entities per call, gains fifteen points from one phrase-table row and its own YAML.

4.4 A recorded limitation

/b/ and /p/ merge for many speakers, so *braces* and *prices* land in one phonetic bucket and edit distance does not separate them either. In practice the confidence condition keeps this from mattering (a recogniser is rarely unsure of *prices*), and `test_a_known_collision_is_documented_not_hidden` exists so that the limitation cannot be quietly lost.

4.5 A real recogniser: pilot on synthetic Indian-English speech

The corruption model is the weakest link in the argument above, so the pipeline that replaces it was built and run before any volunteer was recorded (`research/collect/`). The prompt sentences of every pack (its scenario lines, then entity-bearing frames over its catalogue; 20 per pack) were read by the three Indian-English voices of macOS (`say`: Rishi, Aman, Tara) and transcribed by faster-whisper (`small`, CPU, decoded as English with no hints and no vocabulary), which is the kind of general recogniser Bhasha Bridge is meant to sit on top of. Whisper's per-word probabilities were used as the confidences. This is **synthetic speech through a real recogniser**: it measures real recognition errors on Indian-English synthesis, not on Indian callers, and every file it produced says so.

Table 6 — 300 utterances, 219 catalogue entities, faster-whisper small, English decoding

bridge	WER (%)	EER off (%)	EER on (%)	reduction (%)	precision (%)	beneficial	neutral	harmful
as evaluated in §4.2	88.7	33.8	30.6	9.5	47.1	16	10	**8**
with the guards below	88.7	33.8	30.1	10.8	60.0	12	8	**0**
with the guards and the merged-token rule of §4.9	88.7	33.8	29.2	13.5	60.9	14	9	**0**

Three things the synthetic experiment could not show:

1. **The recogniser's dominant errors are not phonetic substitutions.** Word error rate is 89%: decoded as English, Whisper paraphrases or translates ("Jadavpur wali branch mein tooth extraction ka slot hai kya" became "Is there a slot for tooth extraction in the Jadavpuvali branch?") and merges words ("kal subah root canal" became "KAL SUBHAHROOT KANAL"). Two thirds of the catalogue entities nonetheless survive, because they are English words. The errors that do look like the corruption model's are repaired exactly as designed: *root kanal* → root canal, *giriahat* → Gariahat, *air cut* → haircut, *ms kulakrani* → Ms Kulkarni, *bhavan* → Bhawan, *anapurna* → Annapurna, *need* → NEET. Merged tokens and translated sentences are outside what token-level matching can repair; recogniser biasing, which this run deliberately did not use, is the lever for those.
2. **The confidence gate was open.** The median word probability was 0.62 and 80% of words fell below the 0.85 threshold, so condition 1 of §4.1 held almost everywhere and the layer's safety rested on condition 2 alone. Condition 2 alone is not safe: the bridge made 8 harmful corrections in 300 utterances, 22% of all the corrections it made. Six were *slot* → *Salt*: the Kolkata pack's locality "Salt Lake" contributes the fragment "Salt" to the lexicon, "slot" and "Salt" share the key `SRT`, and they are two edits apart. The others were *na* → *Neha* and *raha* → *Rau*, and a harmless but absurd *to do* → *thyroid profile* through the alias "t3 t4", whose key is `TT` once the digits are dropped.
3. **Three guards close this, and are stated as rules.** Words of the booking dialogue itself (*slot*, *time*, *book*, *branch*, *number*, *raha*, *chahiye*, …) are never corrected, by the same reasoning that already protected grammar words: they are never a tenant's entity, however close their sound key sits to one. A single token of fewer than four letters is never replaced on its own, and a lexicon form with fewer than four letters is never evidence for a replacement; the corruption model never touched such tokens either, which is why the synthetic experiment could not expose this. With the guards the harmful count is zero, precision rises to 60%, and the entity error reduction is 10.8% relative (33.8% → 30.1%). The guards cost three correct repairs of the three-letter surname *Rau* (*rao* → *Rau*). The synthetic results of §4.2 and §4.3 were regenerated with the guards in place; there they remove a handful of neutral corrections and nothing else, and every figure moved within its interval. Per voice the reduction ranges from 20% (Rishi) to none (Aman), on 73 entities each.

The honest summary is that on this data the bridge is safe and helps a little, not that it removes most entity errors as it does under the corruption model. The two numbers differ because the error distributions differ, and the pilot cannot say which one real callers produce: the synthesis is accented but not Hinglish, the recogniser was run in the configuration least favourable to it, and the guards were evaluated on the same 300 utterances that motivated them, so their gain is optimistic. What the pilot establish-

es is the pipeline itself, three failure modes the synthetic harness could not see, and that the confidence gate needs per-recogniser calibration before condition 1 can be trusted. Volunteer recordings through the same pipeline (§9) are the measurement that matters.

4.6 Against the classic keys

The key in §4.1 is one component; the two-condition rule, the edit-distance bound and the lexicon are the rest. To isolate it, the benchmark swaps only the bucketing function and keeps everything else: Soundex (Russell 1918), Metaphone and Double Metaphone (Philips 1990, 2000), NYSIIS, exact spelling (a bucket per spelling, so only identical strings collide), and no bucketing at all (every lexicon form is a candidate and the edit-distance bound alone decides). Each runs on the same 2,430 corrupted sentences per noise level (the §4.2 corpus over all six packs) and on the 300 pilot utterances. McNemar's test on the paired per-sentence outcomes (a sentence has an entity error or not) says whether two keyers differ by more than noise.

Table 8 — Keyers on synthetic noise (transcript level, 2,430 sentences per rate)

keyer	EER on @15%	EER on @30%	EER on @45%	precision @30%	harmful @30%	McNemar vs ours @30%
edit distance only	0.48%	1.45%	2.54%	94.2%	0	b=32, c=13, p = 0.007
exact spelling	17.47%	32.18%	50.65%	100.0%	0	b=936, c=0, p < 0.001
Soundex	2.48%	4.15%	7.72%	98.5%	0	b=118, c=13, p < 0.001
Metaphone	3.88%	8.08%	13.99%	98.6%	0	b=234, c=0, p < 0.001
NYSIIS	1.51%	3.24%	6.81%	99.2%	0	b=90, c=13, p < 0.001
Double Metaphone	2.91%	6.78%	10.63%	98.6%	0	b=193, c=0, p < 0.001
Bhasha (ours)	0.36%	0.88%	2.06%	99.2%	0	—

Entity error with no correction at 30%: 32.2% (identical for every keyer). Bridge off vs ours: b=938, c=0, p < 0.001.

Table 9 — Keyers on the real-recogniser pilot (300 utterances, faster-whisper small)

keyer	EER off	EER on	reduction	precision	beneficial	neutral	harmful
edit distance only	33.8%	31.1%	8.1%	42.0%	34	41	6
exact spelling	33.8%	33.3%	1.4%	50.0%	1	1	0
Soundex	33.8%	30.1%	10.8%	66.7%	14	7	0
Metaphone	33.8%	31.1%	8.1%	63.2%	12	7	0
NYSIIS	33.8%	32.0%	5.4%	76.9%	10	3	0
Double Metaphone	33.8%	30.1%	10.8%	66.7%	14	7	0
Bhasha (ours)	33.8%	29.2%	13.5%	60.9%	14	9	0

Two readings. On synthetic noise the Indic-aware key is clearly better than every classic key (0.88% entity error at 30% noise against 3.2–8.1%, every pairwise McNemar p < 0.001), and better than the edit-distance bound alone (1.45%; b = 32, c = 13, p = 0.007): bucketing does more than restrict the search, it finds forms that are two or three edits away but one sound away. Exact spelling repairs nothing, which is the point of a phonetic key. On the real-recogniser pilot the keys are within a point of each other (29.2% ours, 30.1% Soundex and Double Metaphone, 31.1% Metaphone) and Soundex's precision is higher (67% against 61%): where the recogniser's errors are translations and merged tokens rather than phonetic substitutions, the choice of key barely matters and the guards of §4.5 matter more. Both readings are reported because together they say what the key is for.

4.7 Which rules matter

Each of the 16 normalisation rules was removed in turn and the transcript-level experiment re-run at 30% noise.

Table 10 — Per-rule ablation of the Bhasha key (30% noise; higher delta = the rule matters more)

#	rule	EER on without it	Δ vs full (points)	precision	harmful
8	k/kh/q/c merge	3.51%	+2.63	99.0%	0
4	v/w merge	2.48%	+1.60	98.6%	0
15	h/y dropped	1.21%	+0.33	99.2%	0
0	long a shortens (aa→a)	0.88%	+0.00	99.2%	0
1	ee/ie/ii/iy→i	0.88%	+0.00	99.2%	0
2	oo/uu→u	0.88%	+0.00	99.2%	0
3	ph→f	0.88%	+0.00	99.2%	0
5	s/sh/z merge	0.88%	+0.00	99.2%	0
7	t/d/th/dh collapse	0.88%	+0.00	99.2%	0
9	surviving c→k	0.88%	+0.00	99.2%	0
10	g/gh/j-cluster merge	0.88%	+0.00	99.2%	0
11	b/bh/p merge	0.88%	+0.00	99.2%	0
12	j	0.88%	+0.00	99.2%	0
13	n/m merge	0.88%	+0.00	99.2%	0
14	l/r merge	0.88%	+0.00	99.2%	0
6	ch/chh merge	0.45%	-0.43	99.2%	0

Three rules carry the synthetic result: the k/kh/q/c merge (+2.63 points without it), the v/w merge (+1.60) and the dropped initial h (+0.33); removing the ch/chh merge slightly *helps* (-0.43), because it was merging forms the corpus kept distinct. The twelve rules with a zero delta are not thereby useless: they are not exercised by this corpus under this corruption model, which substitutes a fixed list of confusions on catalogue words. That is a statement about the harness's coverage as much as about the key, and it is one more reason the real-recording study matters: the rules a real recogniser exercises will differ, and this table will be re-run on that data.

4.8 Noise learned from real recognisers, and real telephone Hindi

The corruption model of §3.4 was written by us. To take the author out of the noise, `haanji/corrupt_learned.py` fits a model to a recogniser's own (heard, truth) pairs — word substitutions, character confusions from genuine mishearings, token drops and merges, each at the rate the data showed — and replays it over the benchmark corpus at the recogniser's native rate and at the standard rates. Two sources:

- **Gram Vaani** (OpenSLR 118): rural Hindi telephone speech from community-radio call-ins in Bihar and Jharkhand, with Devanagari transcripts; 110 utterances sampled, transcribed by faster-whisper `small` in Hindi mode, both sides transliterated to Latin script by one deterministic scheme so the comparison is consistent. Word error rate 80.3% (median 80.0%); median word probability 0.657, with 88% of words below the 0.85 gate. The learned model: 44.1% of tokens substituted, 26.0% dropped, 4.9% merged into a neighbour; the commonest character confusions are h→∅, a→∅, n→∅, r→∅, i→∅, ee→i, e→∅, i→a.
- **The pilot of §4.5** (synthetic Indian-English speech through Whisper in English mode): 40.8% substituted, 16.0% dropped, 4.4% merged.

Table 11 — The correction layer under noise learned from real recognisers (transcript level)

noise source	rate	EER off	EER on	reduction	precision	harmful
Gram Vaani (real Hindi telephone speech, Whisper hi)	15%	26.1%	18.89%	27.7%	99.1%	0
Gram Vaani (real Hindi telephone speech, Whisper hi)	30%	49.6%	35.30%	28.8%	97.0%	0
Gram Vaani (real Hindi telephone speech, Whisper hi)	44% (native)	70.5%	50.83%	27.9%	96.0%	0
Gram Vaani (real Hindi telephone speech, Whisper hi)	45%	70.9%	51.47%	27.4%	95.4%	0
pilot (synthetic Indian-English speech, Whisper en)	15%	22.2%	14.80%	33.4%	99.4%	0
pilot (synthetic Indian-English speech, Whisper en)	30%	42.8%	28.73%	32.9%	98.1%	0
pilot (synthetic Indian-English speech, Whisper en)	41% (native)	58.4%	39.69%	32.0%	96.5%	0
pilot (synthetic Indian-English speech, Whisper en)	45%	63.0%	43.69%	30.7%	94.1%	0

Three things follow. First, real recognisers *drop and merge* words at rates the hand-written model never produced (26% of tokens dropped on telephone Hindi): a dropped entity cannot be repaired by any substitution-based layer, so entity error under learned noise is high before correction and stays high after it. Second, within that limit the bridge still does what it claims: a 28% relative reduction at the Gram Vaani native rate and 32% at the pilot's, with precision above 95% and zero harmful corrections, because the confusions a real recogniser makes on *recognised* tokens are the phonetic ones the key was written for. Third, the headline 97% reduction of §4.2 is a property of the hand-written model, which substitutes and never drops; the honest range for "what the bridge removes" is 28–33% of entity errors under data-shaped noise and 96–98% under the authors' model, and the report quotes both. Recognisers that keep tokens (biasing, Hinglish decoding) move a deployment towards the first figure's ceiling; the drops are the next target.

4.9 Merged tokens: a split rule, and the cost it nearly had

The first finding of §4.5 was that Whisper runs words together ("kal subah root canal" came back as "KAL SUBHAHROOT KANAL"), and that no rule over single tokens can repair a token that is two words. The repair added for it is a pre-pass with conditions stated so that each can be tested. A token is split only if it is long (eight letters or more), the recogniser was unsure of it, and the lexicon cannot explain it as a whole, that is, no catalogue form lies within the ordinary rule's reach; it is then split at the first point where both halves are known words (a grammar or frame word, or a word of a catalogue form, each within one edit of its sound key) and at least one half is a catalogue word. "subhahroot" becomes "subah root", and the n-gram pass then repairs "root kanal" as before. Two grammar words glued together are left alone, because a split that frees no catalogue word has nothing to offer.

Table 12 — The merged-token rule on the pilot (300 utterances, English decoding, no hints)

bridge	EER off (%)	EER on (%)	reduction (%)	precision (%)	beneficial	neutral	harmful
guards of §4.5	33.8	30.1	10.8	60.0	12	8	0
guards and the merged-token rule	33.8	29.2	13.5	60.9	14	9	0

Two more entities are recovered in 300 utterances, through two splits ("subhahroot" → "subah root", and in the biased run of §4.11 "democlass" → "demo class" and "subavteet" → "subah teeth"), at no cost in precision and with no harmful correction. The third condition, that the whole token must be unexplained, was not found on the pilot but by the synthetic harness. The first version of the rule split before the ordinary rule ran, and at 30% synthetic noise "Koolkarni", two edits from Kulkarni, became the grammar words "ko karni" before the lexicon saw it: entity error rose from 0.80% to 1.18% with the harmful count still zero, because a neutral correction can pre-empt a beneficial one and the harmful count, defined over the heard token, cannot see that. A probe over the 30% sample (`research/harness/split_probe.py`) counted nine sentences where the split fired, all nine worse; with the ordering condition it fires on none, and Tables 1, 8 and 10 are unchanged by the rule within their in-

tervals. Under the learned noise of §4.8 the rule changes nothing material (Table 11 was regenerated with it: every reduction is identical and precision moves by at most 0.4 points), as expected, since the learned model's merges are of corpus words and the rule touches a merge only when a catalogue word is inside it.

4.10 Calibrating the confidence gate, and finding it is not where the safety comes from

§4.5 ended by saying the confidence gate needs per-recogniser calibration before condition 1 can be trusted. `haanji/bhasha/calibration.py` does the calibration: every word of a (heard, truth) pair is labelled right or wrong by alignment, "confidence below *t*" is treated as a detector of wrong words, the ROC of that detector is drawn, and *t* is set at Youden's J (the largest TPR − FPR); the area under the curve says how much the confidences know at all. The engine loads the result (`Calibration.load`, matched to a recogniser name by longest prefix) into the bridge's `conf_high`.

Table 13 — Calibrated thresholds

recogniser and data	words	wrong (%)	AUC	threshold	TPR	FPR
faster-whisper small, English, the pilot	1,928	65.0	0.67	0.64	0.62	0.34
the same, biased with the pack vocabulary (§4.11)	1,846	50.2	0.62	0.65	0.65	0.44
faster-whisper small, Hindi, Gram Vaani (§4.8)	2,266	69.6	0.77	0.73	0.78	0.38

Table 14 — The gate against downstream entity error on the pilot (English decoding)

gate	0.50	0.60	0.70	0.80	0.85 (default)	0.90 and above, or no gate
EER on (%)	31.5	30.6	31.1	29.7	29.2	29.2
precision (%)	86	67	63	64	61	61
beneficial	6	8	12	14	14	14
harmful	0	0	0	0	0	0

Three things follow. First, the confidences are weakly informative: an AUC of 0.62–0.77 (0.5 is chance) means Whisper's word probability separates its right words from its wrong ones only a little, which is consistent with 80% of all words falling below 0.85 in §4.5. Second, the calibrated thresholds make the bridge worse, not better: at 0.64 the pilot's entity error falls to 31.1% instead of 29.2% (8.1% relative instead of 13.5%), and on the biased run the calibrated 0.65 leaves no correction at all (15.1% → 15.1%), because the calibration optimises the classification of *words* while the quantity that matters is the entity error after a correction layer that already has condition 2 and the guards. Third, the sweep in Table 14 says where the safety actually comes from on this recogniser: the harmful count is zero at every gate including none at all, so condition 1 contributes nothing to safety here, and every tightening of it only removes beneficial corrections. The default therefore stays at 0.85, and the calibration is kept as a tool rather than a setting: a deployment on a recogniser whose confidences are informative runs it on its own pairs in under a minute, and the ROC it records says whether the gate is worth having before the threshold is applied. Two caveats: the thresholds were fitted and the sweep run on the same 300 utterances; and the Gram Vaani pairs carry no catalogue entity, so the Hindi threshold has no downstream test.

4.11 Biasing the recogniser with the pack vocabulary

§4.1 describes the lexicon's surface forms being handed to the recogniser as hints, and §4.5 deliberately withheld them to measure the repair alone. `research/collect/transcribe.py --bias` passes the business's name and its services, staff, places and brands to Whisper as its initial prompt, which is the only biasing mechanism Whisper has (the keyword boosting of a hosted recogniser such as Deepgram is the equivalent on the telephony path), and the same 300 recordings were transcribed again.

Table 15 — Biasing on the pilot (300 utterances, 219 entities; bridge with every rule)

decoding	WER (%)	EER off (%)	EER on (%)	reduction (%)	precision (%)	beneficial	neutral	harmful
English, no hints (Table 6)	88.7	33.8	29.2	13.5	60.9	14	9	0
English, pack vocabulary as the prompt	68.5	15.1	14.2	6.1	42.9	3	4	0

Biasing is the largest single lever in this report. Word error falls by twenty points and the entity error rate *before any repair* halves, from 33.8% to 15.1%, because the recogniser now keeps the catalogue words it was paraphrasing or translating: per pack, Kolkata goes from 37.0% to 5.6% unrepaired entity error, the coaching institute from 31.4% to 9.8%, the salon from 45.1% to 13.7%. After it the bridge has less to do and does it: three beneficial corrections in 300 utterances (*root kanal* → root canal twice, and the split *democlass* → demo class), 6.1% relative, no harmful correction. One correction in the biased run shows a gap in the harmful count: *meen* → Meena, the laboratory's receptionist, from a mishearing of *mein*, invented an entity the caller never said. The harmful count, defined over the heard token, calls it neutral; the entity error rate, which counts spurious entities as well as missed ones, charges it, and it is why the laboratory's row and Tara's row move the wrong way by one entity each (29.4% → 31.4%, 24.7% → 26.0%). Another, *need* → NEET on translated sentences ("We need time for the campus visit"), is neutral by both measures and wrong by inspection: a general recogniser that translates produces English function words that collide with a pack's brands, and that is a guard the pilot suggests but, having been found on the test data, does not yet justify. The reading is that the recommended configuration is both mechanisms, biasing first and the bridge as the safety net behind it, which is what the second row measures; and that the next lever for a deployment is a recogniser that decodes Hinglish natively rather than translating it, which no amount of post-correction can replace.

5. Speculative Turn Execution

5.1 Method

By the time a caller has said "kal subah root canal ka…", it is nearly certain that the next thing needed is tomorrow morning's availability for root canal. The speculation engine (`speculation/engine.py`) receives every partial transcript, asks a cheap predictor for a tool guess, and if the guess is confident enough starts the tool immediately while the caller is still speaking. The predictor is deterministic triggers plus a tiny logistic scorer over bag-of-cue features; a language model here would cost more time than it could save.

The speed is easy; the correctness is the work, and it rests on four properties, each with a test that fails if it is weakened:

- **Purity.** Only tools declared `read_only` in the registry are ever speculated. The registry enforces it; the predictor is not trusted.
- **Argument identity.** A speculative result is claimed only when the real turn asks for byte-identical arguments. Both the predictor and the dialogue policy derive arguments through the same `nlu.py`, which makes the identity structural rather than lucky.
- **Freshness.** Results expire after 4 s and can be claimed exactly once.
- **Invalidation.** Any write voids every result computed against the old world.

A budget bounds the cost of wrong guesses: at most 2 speculations in flight, 3 per turn, and none before 3 words of partial transcript or below a predictor confidence of 0.60. `test_the_result_is_identical_with_speculation_on_and_off` asserts the strong form of the design goal: the transcript of a call must be identical whether speculation is on or off, because it is a latency optimisation and nothing else.

5.2 Results

Table 4 — Ablation on the authored scenarios (clean transcripts)

configuration	task success (%)	EER (%)	read-turn p50 (ms)	read-turn p90 (ms)	write-turn p90 (ms)	all-tool p90 (ms)	spec. hit rate (%)	wasted	unconfirmed writes
full	100.0 ± 0.0	0.0 ± 0.0	142 ± 15	238 ± 26	194 ± 55	220 ± 20	41.9 ± 0.0	54.0	0
no_speculation	100.0 ± 0.0	0.0 ± 0.0	246 ± 8	310 ± 11	194 ± 22	297 ± 5	0.0 ± 0.0	0.0	0
no_bhasha	66.7 ± 0.0	66.7 ± 0.0	167 ± 7	260 ± 30	164 ± 43	224 ± 26	19.2 ± 0.0	63.0	0
baseline	66.7 ± 0.0	66.7 ± 0.0	180 ± 12	275 ± 12	163 ± 40	249 ± 22	0.0 ± 0.0	0.0	0




Figure 3. Engine-side latency of read-only turns (p50, p90) and of write turns (p90), with and without speculation. Nominal milliseconds.

On the authored scenarios with clean transcripts, every configuration with the bridge on reaches the expected outcome in 100.0% of calls, and the two bridge-off configurations fail 8 of the 24, every one of them a scenario whose hand-written corruption hits a catalogue entity (two more such scenarios survive because the dialogue happens to tolerate that particular mangling). Speculation changes no outcome and no transcript. It lowers the median latency of read-only turns from 246 ms to 142 ms (42.3% lower) and the p90 from 310 ms to 238 ms, at a hit rate of 41.9% over 93 speculations per run, saving 218 ms per hit. About 54 speculations per run are wasted, bounded by the budget.

Three things in the table are reported rather than averaged away. First, write turns are never speculated, so the booking turn itself is not faster: its p90 is 194 ms with speculation and without it, and it still waits for the caller's confirmation and the ledger. The p90 over *all* tool turns does fall (297 → 220 ms) only because most tool turns in a booking call are reads. Second, the hit rate is well under 100%: the predictor fires on partials that turn out to want a different date or no tool at all. Third, the two runtime contributions interact: with the bridge off, the hit rate drops to 19.2%, because the predictor derives its arguments from the same mangled entities the policy does, and the real turn then asks for something else. The second and third are the expected shape of a correct speculation scheme, and the second is the quantity a learned predictor trained on real calls would improve.

5.3 Concurrency

Speculation and the policy are measured per call above; a receptionist also has to answer several callers at once. `research/harness/load_test.py` starts one engine process (mock providers, rate limiting off) and drives scripted callers through the web-call API with a short random pause between turns, for a ladder of concurrency levels, measuring the HTTP round-trip of each turn — what a browser or a telephony bridge would wait for.

Table 7 — one process, scripted callers, 21 scripts across the five packs

concurrent callers	calls	turns	p50 (ms)	p95 (ms)	max (ms)	calls/min	errors	expected outcome
5	60	157	6.9	188.5	192.8	457	0	98%
10	60	157	5.6	185.0	189.9	786	0	97%
25	60	157	3.9	183.8	185.3	1399	0	88%
50	60	147	6.1	185.8	196.8	2146	0	75%




Figure 4. Turn latency over HTTP (p50, p95, max) as concurrency rises. One process; the p95 is the booking turn's write and ledger seal.

Latency is flat across the ladder and no request fails; throughput scales with concurrency because the engine's own work per turn is a few milliseconds and the rest is waiting. The expected-outcome rate falls because all callers in a level share one tenant calendar and ask for the same morning: once it is full the agent correctly offers another time or takes a callback, which the fixed script does not follow, so those calls end abandoned or as leads. That is the calendar working, not the engine failing, and it is why the column is reported next to the error count rather than folded into it. The numbers are engine-side; a speech vendor's round trip and a telephony hop will dominate a deployment, and this measurement says only that the engine will not be the bottleneck before them.

Cost. The engine process spent 0.0085 CPU-seconds per call (3.28 CPU-ms per turn) across the ladder; on a ₹600/month single-vCPU instance that is ≈ ₹0.000000 of infrastructure per call (0.0 millionths of a rupee), against the ₹0.20 the cost model in `insights.py` assumes — the assumption is conservative by five orders of magnitude, and the per-minute speech vendors (telephony ≈ ₹0.50, recognition ≈ ₹0.90, synthesis ≈ ₹0.45 per minute) are the whole of the ≈ ₹3 per call. A receptionist at ₹12,000 a month answering 50 calls a day costs ≈ ₹9.2 per call.

5.4 A learned predictor, and why the hand-set one stays

§5.2 named the hit rate as the headroom a learned predictor would take. `research/harness/predictor_fit.py` tries it on the data the harness has. Every partial transcript of every scenario is logged (156 partials over the six packs, 44 of them followed by a read-only tool call in the real turn), each with the eight features the hand-set scorer uses (date, time and booking words, question, identity and cancel words, length, and whether a service is mentioned); a logistic predictor is fitted by gradient descent, validated leave-one-pack-out, refitted on everything, and then run through the benchmark against the hand-set weights.

Table 16 — Hand-set against fitted predictor

	precision	recall	hit rate (%)	speculations started	wasted	read-turn p50 (ms)
hand-set weights	0.86	0.82	41.9	93	54	116
fitted weights	1.00	0.71	44.4	81	45	160

Cross-validation gives precision 1.00 in every held-out pack and recall from 0.25 (coaching institute) to 1.00. The benchmark row is a single run at the harness's default settings: its hit rate agrees with Table 4's five-seed mean and its latencies are one sample of that distribution; the comparison within the row is paired. The fitted predictor is cautious: it never fires on a partial that wants no tool, misses three in ten that do, starts 13% fewer speculations, wastes fewer, and lifts the hit rate by two and a half points; and the median read turn is 44 ms *slower*, because the turns it declines are exactly the ones where a hit saves the most. For latency, recall is what matters: a wasted speculation costs an otherwise idle engine a cheap read, a missed one costs the caller the whole tool time. The hand-set weights therefore stay the

default, and the fitting script is kept as the harness for the data that would change the answer, partials from real calls, which the live feed of the demo server records as they happen.

6. Pramaan Ledger

6.1 Method

Every write (`book_appointment`, `cancel_appointment`, `capture_lead`, `handoff`) produces a receipt containing the action and its arguments, a *confirmation proof* (the exact sentence the agent asked, the exact words the caller replied, when each began, the offset between them, and the recogniser's confidence in the reply), a redacted transcript excerpt, the pack version, and a timestamp. The payload hash is SHA-256 over the canonical JSON (sorted keys, no insignificant whitespace, RFC 8785 in spirit) of those fields; the chain hash is SHA-256 over the previous chain hash and the payload hash; the chain hash is signed with the tenant's Ed25519 key. A day's receipts are anchored by a signed Merkle root. The receipt's short code (the first eight hex digits of the chain hash) is what the agent reads to the caller: "Confirmation code 2504-7863".

Two consequences follow that a log file cannot give:

- **The ledger refuses an unconfirmed write.** Appending with no confirmation proof raises inside the transaction, which rolls back, and no booking exists. This is enforced in the ledger, below the dialogue policy, so a policy bug (or a hosted model's hallucinated tool call, §7) cannot book something the caller did not agree to.
- **Anyone can check it.** The export endpoint returns receipts and the public key and nothing else. `haanji verify` and the public `/verify` page re-derive every hash and check every signature without trusting the platform; the page has a *tamper* button so a visitor can watch the chain break.

6.2 Results

Table 5 — Pramaan Ledger under attack (deterministic)

attack	attempted	detected
mutate `action_args.time`	10	10
mutate `action_args.service`	10	10
mutate `action_args.phone`	10	10
mutate `confirmation.reply_text`	10	10
mutate `confirmation.asr_confidence`	10	10
mutate `transcript_excerpt`	10	10
mutate `occurred_at`	10	10
mutate `agent_config_version`	10	10
delete a receipt from the middle	1	1
forge a receipt and re-hash it	1	1
write without a confirmation proof	1	1

The experiment seals a chain of 40 real bookings, then attacks it: each of eight fields is mutated in ten receipts; a receipt is deleted from the middle; a receipt is forged and conscientiously re-hashed so that its own hashes are consistent; and a write with no proof is attempted. Every mutation is caught at the payload hash, the deletion at the chain hash, the forgery at the signature, and the unconfirmed write at the ledger's door. The end-to-end harness additionally scans every backend after every call for a confirmed booking without a receipt code and found none in any configuration or seed (Table 4, last column). These results are deterministic and are reported without intervals.

7. Dialogue: a deterministic policy, and a hosted model behind the same boundary

The policy in §3.3 answers every call in the evaluation above. It was chosen for auditability and speed, and its limitation is obvious: it understands the phrasings its authors anticipated. To measure what a hosted model buys and costs, the engine's dialogue boundary was made real (both halves of a turn,

planning and reacting to tool results, go through one `respond()` call) and an adapter for Claude (`claude-opus-4-8`) was written behind it with three properties:

- **The model never decides a write.** A request to book or cancel is intercepted and turned into the pack's own read-back question; the caller's "haan" is then handled by the deterministic policy, which is the only path that produces a tool call the ledger will accept. The write path is therefore identical with or without the model, and the ledger's guarantee does not depend on prompt quality.
- **Vendor failure falls back to the policy for that turn**, so a call never dies because an API did.
- **Guardrails and speculation are unchanged.** Speculation's predictor derives arguments through `nlu.py`; the model's arguments will often differ, so the hit rate is expected to fall, and this is measured rather than hidden.

The adapter is validated offline with a scripted stand-in for the API (ten tests: text replies, a read-only round trip with matching tool-use ids, a write turned into the confirmation question, a confirmed yes producing a receipt while the model is not consulted, end-of-call, fallback). The ablation harness `research/harness/llm_ablation.py` runs the 21 scenarios under both adapters:

	deterministic policy (`mock`)	Claude (`claude`)
scenarios reaching expected outcome	21/21	*not yet run*
receipts written	16	—
turn latency p50 / p95, engine-side (ms)	32 / 176	—
speculation hits / started	12/26	—
adapter calls / fallbacks	81 / 0	—

The Claude column is empty in this version of the report because the run requires an API key and had not been executed when the report was generated; the harness skips it with a note rather than inventing a number. The column will be filled in version 1.1 with the same script. What the design already guarantees, independent of that run, is that the receipts column will be produced by the same code path and the unconfirmed-writes count will be zero.

8. Threats to validity

Construct. Entity error rate is defined over the catalogue entities the pack declares; a recogniser error in a date word or a phone number is invisible to it, though not to task success, which is why both are reported. "Task success" is agreement with the outcome the scenario author expected, which for handoffs and refusals is the right behaviour, not a booking.

Internal. The corruption model is a model: it reproduces the substitutions Indian-English recognisers make, in the directions they make them, but it was written by the same team as the correction layer. We mitigated this by making it corrupt words outside every lexicon and by counting harmful corrections explicitly; the zero harmful count under it is evidence the layer is conservative on that distribution, and §4.5 shows it was not conservative on a real recogniser's distribution until two of its assumptions (calibrated confidence, no very short tokens) were made explicit. The guards were then evaluated on the data that motivated them, and so were the merged-token rule, the calibrated thresholds and the gate sweep of §4.9–4.10 and the biasing comparison of §4.11: all on the same 300 pilot utterances, so each gain is optimistic in the same way. Scenarios are scripted, so a clarification question the caller "does not answer" counts as a failure the way a real caller would not. Speculation is measured against the mock recogniser's partials, which arrive at a realistic word rate but with no real acoustic uncertainty.

External. All latencies are engine-side, under simulated time, on one machine: they measure what HaanJi adds and what speculation removes, not vendor round-trip time, which in a deployment will dominate. No real audio was recognised and no real caller was involved in any number above; the browser demo and the WhatsApp channel have handled real text and speech, but informally. Five packs and 21 scenarios are a small, author-written sample of Indian small businesses.

Statistical. Confidence intervals are over 5 seeds with 3 repetitions each, using the t-distribution; with so few seeds the intervals are honest but wide, and a difference whose intervals overlap should be read as "not separated by this experiment". Several quantities (harmful corrections, unconfirmed writes, ledger detections) have zero variance because they never moved; that is the design working, not a statistical artefact, and it is why they are also covered by tests that fail if they change.

9. Limitations and future work

1. **Real recordings.** The pipeline is in place (`research/collect/`): a recording page (`/record`) that walks a volunteer through the pack's prompt sentences, a transcription script over a local Whisper model, and the same entity-error scoring over the resulting (heard, truth) pairs. §4.5 reports a pilot on synthetic Indian-English speech; what remains is 50–100 utterances from volunteers. If the entity error reduction holds on recorded callers the claim becomes a paper-grade one; if it does not, that is the finding.
2. **Real users.** The study kit is in place: a protocol (`docs/study/protocol.md`), a participant page (`/study`) with consent, three timed task cards and the System Usability Scale (Brooke 1996) in Hinglish, and an analysis script that reports task success with Wilson intervals and SUS with a t-interval. The study itself (8–10 participants) has not been run.
3. **The hosted-model ablation** (§7) with the key in place, including the speculation hit rate under model-derived arguments and a token-cost line.
4. **Out-of-lexicon failures.** The calls that still fail under noise are ones where a date or number word was corrupted. A separate, small closed-vocabulary repair for dates, times and numbers, with the same two-condition rule, is the obvious next layer.
5. **Telephony.** A Twilio Media Streams bridge with streaming recognition (Deepgram) and synthesis (ElevenLabs) is built and tested against fakes; a real call has not been placed, and vendor latency is the quantity to measure when one is.
6. **A learned predictor.** Tried in §5.4 on the harness's own partials: more precise, less eager, and slower at the median, so the hand-set weights stay. The version that could change that trains on partials from real calls, which the live feed records.
7. **A Hinglish-capable decoder.** Biasing (§4.11) halves entity error before any repair; a recogniser that decodes code-mixed speech natively, or Whisper's Hindi mode with the transliteration of §4.8, is the next experiment on the same 300 files, and the one most likely to move the pilot's numbers.

10. Conclusion

A voice receptionist for Indian small businesses fails for three specific reasons: it does not know the business's words, it is slow at the turn, and it cannot prove what was agreed. HaanJi addresses each with a mechanism that is small, inspectable and measured. Bhasha Bridge removes most catalogue entity errors under heavy synthetic noise without damaging a correct transcript, and the gain survives into end-to-end task success and into a second language; on a real recogniser's output it needed two more stated rules to stay safe and then helped far less, and under noise learned from real telephone Hindi it removes about a third of the entity errors rather than nearly all, because real recognisers drop words as often as they mangle them. That measurement sent the next piece of work to recogniser biasing, which was then tried: with the pack vocabulary in the recogniser's prompt, entity error halves before the bridge runs, and the bridge's role becomes the safety net behind it. Calibrating the bridge's confidence gate turned out not to matter, and the report says so: on Whisper's probabilities the gate contributes nothing to safety, the stated guards and the second condition carry all of it. Speculative Turn Execution takes a large fraction off the median read-turn latency while leaving every transcript identical. The Pramaan Ledger makes every booking carry its own evidence and makes an unconfirmed booking impossible rather than unlikely, a property that holds whether the dialogue is driven by the deterministic policy or by a hosted model. The evaluation is reproducible from a clean checkout and is honest about its synthetic origins; the next two studies replace synthetic noise with real recordings and scripted callers with real ones.

References

Bali, K., Sharma, J., Choudhury, M., and Vyas, Y. (2014). "I am borrowing ya mixing?" An analysis of English-Hindi code mixing in Facebook. *Proceedings of the First Workshop on Computational Approaches to Code Switching*, EMNLP 2014.

Bernstein, D. J., Duif, N., Lange, T., Schwabe, P., and Yang, B.-Y. (2012). High-speed high-security signatures. *Journal of Cryptographic Engineering*, 2(2), 77–89.

Bohus, D., and Rudnicky, A. I. (2005). Sorry, I didn't catch that! An investigation of non-understanding errors and recovery strategies. *Proceedings of the 6th SIGdial Workshop on Discourse and Dialogue*.

Brooke, J. (1996). SUS: A "quick and dirty" usability scale. In P. W. Jordan et al. (eds.), *Usability Evaluation in Industry*. Taylor & Francis.

Budzianowski, P., Wen, T.-H., Tseng, B.-H., Casanueva, I., Ultes, S., Ramadan, O., and Gašić, M. (2018). MultiWOZ: A large-scale multi-domain Wizard-of-Oz dataset for task-oriented dialogue modelling. *Proceedings of EMNLP 2018*.

Chen, C., Borgeaud, S., Irving, G., Lespiau, J.-B., Sifre, L., and Jumper, J. (2023). Accelerating large language model decoding with speculative sampling. arXiv:2302.01318.

Haber, S., and Stornetta, W. S. (1991). How to time-stamp a digital document. *Journal of Cryptology*, 3(2), 99–111.

Hennessy, J. L., and Patterson, D. A. (2017). *Computer Architecture: A Quantitative Approach* (6th ed.). Morgan Kaufmann.

Javed, T., Joshi, S., Nagarajan, V., et al. (2023). Svarah: Evaluating English ASR systems on Indian accents. *Proceedings of Interspeech 2023*.

Javed, T., Nawale, J. A., George, E. G., et al. (2024). IndicVoices: Towards building an inclusive multilingual speech dataset for Indian languages. *Findings of the Association for Computational Linguistics: ACL 2024*.

Laurie, B., Langley, A., and Kasper, E. (2013). Certificate Transparency. RFC 6962, IETF.

Levenshtein, V. I. (1966). Binary codes capable of correcting deletions, insertions, and reversals. *Soviet Physics Doklady*, 10(8), 707–710.

Leviathan, Y., Kalman, M., and Matias, Y. (2023). Fast inference from transformers via speculative decoding. *Proceedings of the 40th International Conference on Machine Learning (ICML 2023)*.

Merkle, R. C. (1987). A digital signature based on a conventional encryption function. *Advances in Cryptology, CRYPTO '87*, LNCS 293, 369–378.

Philips, L. (1990). Hanging on the Metaphone. *Computer Language*, 7(12), 39–43.

Philips, L. (2000). The Double Metaphone search algorithm. *C/C++ Users Journal*, 18(6).

Pundak, G., Sainath, T. N., Prabhavalkar, R., Kannan, A., and Zhao, D. (2018). Deep context: End-to-end contextual speech recognition. *Proceedings of the IEEE Spoken Language Technology Workshop (SLT 2018)*.

Radford, A., Kim, J. W., Xu, T., Brockman, G., McLeavey, C., and Sutskever, I. (2023). Robust speech recognition via large-scale weak supervision. *Proceedings of ICML 2023*.

Rundgren, A., Jordan, B., and Erdtman, S. (2020). JSON Canonicalization Scheme (JCS). RFC 8785, IETF.

Russell, R. C. (1918). Index. U.S. Patent 1,261,167.

Skantze, G. (2005). Exploring human error recovery strategies: Implications for spoken dialogue systems. *Speech Communication*, 45(3), 325–341.

Zhao, D., Sainath, T. N., Rybach, D., Rondon, P., Bhatia, D., Li, B., and Pang, R. (2019). Shallow-fusion end-to-end contextual biasing. *Proceedings of Interspeech 2019*.

Appendix A. Reproducing every number

```
git clone https://github.com/aritra-25hazra/haanji && cd haanji/engine
python3.11 -m venv .venv && source .venv/bin/activate
pip install -e ".[dev,web,llm,research]"
pytest -q                                   # 317 tests, about 6 s
python -m haanji.cli selftest               # 24 scenarios reach their expected outcome
python -m haanji.bench --reps 5 --speed 90  # research/results.json, about 3 min
cd .. && python research/harness/report_data.py --seeds 5 --reps 3 --speed 90
                                            # report_data.json, report_tables.md, figures/
python research/harness/llm_ablation.py     # needs ANTHROPIC_API_KEY for the claude half
python research/collect/synth.py && python research/collect/transcribe.py --manifest
research/collect/data/synthetic/manifest.jsonl --out
research/collect/data/synthetic/pairs.jsonl && python research/collect/evaluate.py --pairs
research/collect/data/synthetic/pairs.jsonl
                                            # the §4.5 pilot (macOS voices, faster-whisper)
python research/harness/baselines.py        # §4.6–4.7: research/baselines.json
python research/harness/learned_noise.py    # §4.8: research/learned_noise.json (needs the
Gram Vaani pairs)
python research/harness/split_probe.py      # §4.9: where the merged-token rule fires on
synthetic noise
python research/harness/calibrate.py        # §4.10: research/calibration.json
python research/collect/transcribe.py --bias --manifest
research/collect/data/synthetic/manifest.jsonl --out
research/collect/data/synthetic/pairs_biased.jsonl && python research/collect/evaluate.py --
pairs research/collect/data/synthetic/pairs_biased.jsonl --out research/real_asr_biased.json
                                            # §4.11: the biased pilot
python research/harness/predictor_fit.py    # §5.4: research/predictor_fit.json
python research/harness/load_test.py        # §5.3: research/load_test.json
python research/harness/report_pdf.py       # this document as PDF; --paper for
research/PAPER.pdf
```

Appendix B. The packaged scenarios (24)

pack	scenario	expected outcome	caller turns	what it exercises
dental_clinic	booking_with_asr_noise	BOOKED	5	service and locality mangled by the recogniser
dental_clinic	price_question_then_book	BOOKED	5	FAQ followed by a booking in one call
dental_clinic	faq_only	FAQ_ANSWERED	2	knowledge base, no booking
dental_clinic	emergency_handoff	HANDED_OFF	1	guardrail: emergency leaves automation at once
dental_clinic	medical_advice_refusal	HANDED_OFF	1	guardrail: the agent must not diagnose
dental_clinic	no_slot_lead_capture	LEAD_CAPTURED	2	closed day; a missed booking becomes a lead
dental_clinic	caller_interrupts	BOOKED	4	barge-in; synthesis stops mid-sentence
dental_clinic	doctor_by_name	BOOKED	5	"Dr Sheikh" heard as "Shaikh"; the staff list repairs it
salon_spa	colour_booking	BOOKED	4	multi-word service, staff preference
salon_spa	monday_closed_lead	LEAD_CAPTURED	2	weekly closure
salon_spa	price_faq	FAQ_ANSWERED	2	catalogue price
salon_spa	complaint_handoff	HANDED_OFF	1	escalation rule
diagnostic_lab	fasting_test_booking	BOOKED	4	prep note read back with the slot
diagnostic_lab	report_interpretation_refusal	HANDED_OFF	1	guardrail: no interpretation of results
diagnostic_lab	fasting_faq	FAQ_ANSWERED	2	knowledge base
coaching_institute	demo_booking	BOOKED	4	demo-class booking
coaching_institute	fee_faq	FAQ_ANSWERED	2	fees from the catalogue
coaching_institute	rank_promise_refusal	HANDED_OFF	1	guardrail: no guarantees
clinic_kolkata	benglish_booking_with_noise	BOOKED	4	Benglish; service mangled, repaired from the lexicon
clinic_kolkata	benglish_price_faq	FAQ_ANSWERED	2	Benglish knowledge base
clinic_kolkata	benglish_emergency	HANDED_OFF	1	Benglish guardrail
clinic_pune	marathi_booking_with_noise	BOOKED	4	Marathinglish; service mangled, repaired from the lexicon
clinic_pune	marathi_price_faq	FAQ_ANSWERED	2	Marathinglish knowledge base
clinic_pune	marathi_emergency	HANDED_OFF	1	Marathinglish guardrail

Appendix C. Test inventory (317 tests)


file	tests	
test_pipeline.py	34	the turn controller, barge-in, confirmation flow, receipts per call, speculation on/off identity,
test_web.py	30	the demo server, design tokens, relative URLs, no emoji (every page, including th
test_packs.py	29	every pack validates and every scenario re
test_bhasha.py	28	the two-condition rule, name protection, harmful-correction detection, the pilot's guards, the merged-token rul
test_phonetics.py	24	each key rule, the kn
test_backend_guardrails.py	24	availability, bookings, guardrail subj
test_pramaan.py	19	chain, signatures, refusal of unconfirmed writes, ver
test_speculation.py	14	purity, argument identity, freshness, in
test_claude_adapter.py	10	the hosted-model adapter and its
test_whatsapp_webhook.py	9	Meta signature, c
test_auth.py	9	one-time codes over WhatsApp, signed scoped tokens, roles, per-pa
test_research_kit.py	8	the recording page, the study page, scoring of rea
test_trust.py	6	receipt links in replies, daily anchors and their signatures,
test_text_channels.py	6	the WhatsApp simula
test_pramaan_properties.py	6	property-based: random receipts and mutations; truncation is caught by the anc
test_onboard.py	5	the onboarding wizard's draft is a valid pack whose generat
test_devanagari.py	5	transliteration both ways, the toggle endpoint, a
test_calendar.py	5	iCalendar feed, per-booking .ics, Google Calend
test_telephony.py	4	the Twilio media-stream bridge with fake recognise
test_reschedule.py	4	a booking moved through the ordinary confirmation flow and sealed with it
test_privacy.py	4	the per-customer vault, access and erasure,
test_live.py	4	the event bus and th
test_hardening.py	4	security headers, per-client rate limiting of writes, the signed
test_calibration.py	4	ROC, Youden's J, loading thresho
test_takeover.py	3	human takeover and hand-back; WhatsApp wa
test_stats.py	3	McNemar and th
test_ops.py	3	Prometheus text, spans and the ops view, the refu
test_marathi.py	3	the third lan
test_corrupt_learned.py	3	the learned corruption mod
test_benglish.py	3	the second lan
test_study_analysis.py	2	the study sum
test_push.py	2	VAPID keys, subscriptions, droppin

Appendix D. Diagrams


The system as a reader of the code expects to see it drawn. (Also at `docs/diagrams.md`.)

The system as examiners expect to see it: context, containers, a booking turn, the data, the data flow, the classes that matter, and the deployment. All Mermaid, so they render on GitHub and in the PDF report.


C4 — context




C4 — containers




Sequence — one booking turn (speculation, correction, confirmation, receipt)




ER — the data




DFD — level 0 and level 1



Level 0
Caller
speech
reply, receipt code
HaanJi
insights, digest, calendar
pack, settings
Owner



Class diagram — the engine's core


CallSession
+open(phone)
+handle_utterance(utt)
+handle_partial_text(text)
+handle_text_turn(text, confidence)
+finish() : CallReport
BhashaBridge
+correct(Transcript) : CorrectedTranscript
+hints()
SpeculationEngine
+on_partial(text, ctx)
+claim(tool, args)
+on_write()
«interface»
LLMAdapter
+respond(system, history, tools) : LLMTurn
Guard
+check(text) : Verdict
ToolRegistry
+register(tool)
+execute(name, args)
+is_read_only(name)
TenantLexicon
+build(seed)
+candidates(key)
+reinforce(surface, delta)
IntentPredictor
+predict(partial, ctx) : ToolGuess
MockLLM
ClaudeLLM
Ledger
+append(args) : Receipt
+receipts(tenant)
+anchor_day(tenant, day)
DialoguePolicy
+plan(text, ctx) : LLMTurn
+after_tools(text, ctx, results) : LLMTurn
+ask_confirmation(ctx, action, args) : LLMTurn
Receipt
+compute_payload_hash()
+compute_chain_hash()

Deployment


auto deploy
vercel deploy --prod
Vercel — console
haanji-kappa.vercel.app
/engine/* rewrite
Google Calendar
ElevenLabs
Meta WhatsApp
signed webhook
Render — engine container
haanji-
engine.onrender.com
Twilio
voice webhook + media
stream
Deepgram
/metrics
Prometheus
Grafana
Developer / Codespaces
git push main
GitHub
CI, CodeQL, gitleaks, SBOM
daily workflow
anchors
transparency branch
signed daily roots